

GENERAL NOTES (DEMARCATIION)

1. STANDARD SPECIFICATION

All works shall comply with technical standards specified herein and other revisions deemed necessary by LLDA.

2. DIMENSIONS

Unless otherwise stated all measurements shall be measured in meters.

3. MOBILIZATION

Refers to the transport of materials, like Anahaw poles, Bamboo poles, and other materials, from the source to the staging area in Binangonan port to each of the specific zones. The transport cost is expected to vary from zone to zone depending on the distance.

4. ALIGNMENT

No alteration or change in alignment shall be made unless existing field condition so warrant and only upon written order by the personnel and approved by the proper authority concerned.

5. STANDARD STACKING LOCATIONS

The staking locations are based on the GPS Coordinates obtained by the Authority with the use of Google earth shall be utilized for the project unless otherwise stated.

6. PRELIMINARY SURVEY/DEMARCATIION

Preliminary survey shall be conducted so as to mitigate the margin of error generated from obtaining the coordinates in google earth.

7. TIME LINE

The project duration shall not exceed 105 working days and will be done in phases

PHASE	ZONE	LOCATION	ACTIVITY	DURATION
I	A	Taguig and Muntinlupa	Preliminary Surveying with Stacking/Demarcation	20 Working Days
II	B	San Pedro, Biñan, Sta. Rosa, Calamba, Los Baños, and Bay	Preliminary Surveying with Stacking/Demarcation	20 Working Days
III	C	Victoria, Sta. Cruz, Lumban, Kalayaan, Paete, Pangil, Pakil, Siniloan, Mabitac, and Jala-Jala East	Preliminary Surveying with Stacking/Demarcation	30 Working Days
IV	D	Cardona-Main, Tanay, Morong, Baras, Pila, Pililla, and Jala-Jala west	Preliminary Surveying with Stacking/Demarcation	25 Working Days
V	E	Binangonan-Main and Angono	Preliminary Surveying with Stacking/Demarcation	10 Working Days
<u>TOTAL PROJECT DURATION</u>				<u>105 Working Days</u>

✓

